

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2021-22/OW/WORK_INDENT50206

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/14/2021-22, Date: 14-02-2022

Name of Work: Improvements to roads and drains in 1st main road, 1st cross, Ravishankara residency Sanjeevininagara in ward no. 07 Byatarayanapura.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of U RAMESH ()	
				In Figures	In Words
1	402.38	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications.	Cum	137.0	Rupees One Hundred Thirty Seven Only
2	14.63	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials labour, HOM curing, form works, scaffolding and centering complete as per specification.	Cum	5421.0	Rupees Five Thousand Four Hundred Twenty One Only
3	234	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. 7.5 cm thick	Sqm	742.0	Rupees Seven Hundred Forty Two Only
4	123.5	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage ' of mixed Material by tipper to site, laying in uniform layers with paver in sub- base/ base course on well prepared surface and compacting with vibratory roller to achieve the desired density. complete as per specifications.	Cum	2001.0	Rupees Two Thousand One Only
5	617.5	Providing and applying primer coat with SS bitumen emulsion on prepared surface of granular Base such as WBM WMM including clearing of road surface and spraying primer at the rate of 0.60 kgsqm using mechanical means complete as per specifications.	Sqm	29.3	Rupees Twenty Nine and Thirty Paise Only
6	24.7	Providing and laying bituminous concrete 40 mm compacted thickness with VG30 Bitumen grade using 40-60 HMP using crushed aggregates of grading II, premixed with bituminous binder at 6% of mix and filler, transporting the hot mix to work site, laying with a mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRT&H specification clause No. 500.9 complete in all respects as per specifications.	Sqm	8981.0	Rupees Eight Thousand Nine Hundred Eighty One Only
7	13	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications.	Sqm	455.0	Rupees Four Hundred Fifty Five Only

U. Ramesh
Signature of the Contractor

11/5/22
[Signature]
Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92